



## Contents

1	Crea	ating Controller CA Certificate	. 3
		ating Controller Certificate and Private Key	
3	Run	ning Controller with Switch CA Certificate	. 3
4	Run	ning Switch with Controller CA Certificate	. 3
5	Run	ning MuL with OpenSSL	. 4
	5.1	Without switch CA certificate	. 4
	5.2	With switch CA certificate	. 4



## 1 Creating Controller CA Certificate

Controller CA certificate can be created by using the following command:

root@sdn-server:~# cd utils/ssl-cert root@sdn-server:~# sudo ./mul-pki-cmd init

This command will create the Controller CA certificate and initializes the PKI infrastructure to create the controller certificate and controller private key.

## **2** Creating Controller Certificate and Private Key

This command will generate and install the Controller Certificate and Controller private key to /etc/mul/.

### Example:

root@sdn-server:~# sudo ./mul-pki-cmd req+sign+install ctl controller

# 3 Switch CA Certificate for Controller usage (Optional)

If vendor wants to run Mul Controller with strict Switch CA certificate validation then vendor should copy switch CA certificate to /etc/mul/switch\_ca.crt

Note: This is an optional step. MuL controller can run with or without switch CA certificate. For options of running MuL with or without Switch CA certificate, refer section 5.

### 4 Controller CA Certificate for Switch usage

If vendor needs Mul Controller CA certificate then vendor should copy controller CA certificate from /etc/mul/pki/controllerca/cacert.pem to the switch location.



### **5** Running MuL with OpenSSL

### 5.1 Without switch CA certificate

```
root@sdn-server:~# sudo ./mul -s
2014/02/06 15:41:28 MUL: [THREAD] INIT |4| switch-threads |2| app-threads
2014/02/06 15:41:28 MUL: [HA] Init
2014/02/06 15:41:28 MUL: [APP] mul-vty registered
2014/02/06 15:41:42 MUL: [SWITCH] Pinned to thread |1|
```

#### 5.2 With switch CA certificate

```
root@sdn-server:~# sudo ./mul -s -x
2014/02/06 15:41:28 MUL: [THREAD] INIT |4| switch-threads |2| app-threads
2014/02/06 15:41:28 MUL: [HA] Init
2014/02/06 15:41:28 MUL: [APP] mul-vty registered
2014/02/06 15:41:42 MUL: [SWITCH] Pinned to thread |1|
```

Note: Option '-x' is used to by MuL to validate switch CA certificate.

